U.S. DEPARTMENT OF AGRICULTURE FOREST SERVICE **TIMBER SALE CONTRACT** (Applicable to Sales to be Scaled after Felling)		**Name of Purchaser**	
National Forest Idaho Panhandle	**Ranger District** Saint Maries	**Region** Northern	**Contract Number**
Sale Name Cedar Side Boards		**Award Date**	**Termination Date** 10/31/2013

The parties to this contract are The United States of America, acting through the Forest Service, United States Department of Agriculture, hereinafter called Forest Service, and _____ hereinafter called Purchaser.

Forest Service having advertised a sale at which either (1) Purchaser, whose required bid deposit is now held by Forest Service as an initial deposit, was the successful bidder, or (2) no bids were received and Purchaser having subsequently offered at least the minimum advertised price and made an initial deposit in the same amount as the bid deposit specified in the sale advertisement; and the parties hereto desiring to record their agreement; now therefore,

Unless provided otherwise herein, Forest Service agrees to sell and permit Purchaser to cut and remove Included Timber and Purchaser agrees to purchase, cut, and remove Included Timber.

This contract consists of three Divisions: A - Specific Conditions, B - Standard Provisions, and C - Special Provisions, together with Sale Area Map, Plans and specifications for developments (if any), and such attachments as may be provided for in Division C. Specific Conditions are numbered and apply to the Part, Section, Subsection, or Item of the Standard Provisions, as indicated hereunder. Other conditions of this contract are stated in Division C - Special Provisions.

IN WITNESS WHEREOF, the parties hereto have executed this contract as of the award date.

UNITED STATES OF AMERICA

Two Witnesses: 1/

By: _____
Contracting Officer

_____
(Name)

_____
(Title)

_____
(Address)

_____
(Purchaser) 2/

_____
(Name)

By: _____

_____
(Address)

_____
(Title)

_____
(Business Address)

I,3/ _____, certify that I am the _____
Secretary of the corporation named as Purchaser herein; that _____
who signed this contract on behalf of Purchaser, was then _____
of the corporation; that the contract was duly signed for and in behalf of the corporation by authority of its governing body, and is within the scope of its corporate powers.

_____ **CORPORATE SEAL** 4/

INSTRUCTIONS:

1/ The signatures and addresses of two witnesses are required if Purchaser is other than a corporation.

2/ If Purchaser is a co-partnership, the signatures should be: XYZ Company, by John Doe, a member of the firm. If Purchaser is a corporation, form of signature should be: XYZ Company, by John Doe, President (or other officer or agent) and the seal of the corporation must be impressed or indicated.

3/ The certificate must be completed if Purchaser is a corporation.

4/ If the corporation has no corporate seal that fact shall be stated, in which case a scroll or adhesive seal shall follow the corporate name.

EXAMPLE 1/

Subcontractor Certification
Regarding Debarment, Suspension, Ineligibility, and Voluntary Exclusion

Timber Sale Name: _____
National Forest: _____

The prospective subcontractor (participants in lower tier covered transactions) certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this timber sale by any Federal department or agency.

Where the prospective subcontractor is unable to certify to any of the statements in this certification, such prospective subcontractor shall attach an explanation to this proposal.

Name of Subcontractor: _____
Business Address: _____
_____

_____ _____
Date Signature

1/ It is the Purchaser's responsibility to have subcontractors complete this certification and to maintain a file of completed certifications. This certification does not need to be returned to the Forest Service, except at the written request of the Contracting Officer.

The following conditions apply to the indicated portions of Division B – Standard Provisions issued June 2006.

A1 – Location and Area, applicable to B1.1

This Sale Area of 3351 acres more or less is located in: Sections 35 & 36, T43N, R1E, Sec 1,2,3,11,12, T42N, R1E, Sec 6,7, T42N, R2E and 31, T43N, R2E, Boise Meridian, Shoshone County, Idaho

A2 – Volume Estimate and Utilization Standards, applicable to B2.1, B2.2, B2.4, and B6.4

				Minimum Specifications				
				Merchantable Tree		Piece Required to be Removed		
Species	**Product**	**Estimated Quantity**	**Unit of Measure**	**Diameter Breast High (d.b.h.)** *(inches)*	**Number of Minimum Pieces per Tree**	**Length** *(feet)*	**Diameter Inside Bark at Small End** *(inches)*	1/
Combined Softwood	Sawtimber	20,110	Ton	7	1	8	5.6	10.67
Combined Softwood	Non Sawtimber	1394	Ton	N/A	1	9	4.0	100% Sound
Timber Subject to Agreement under C2.11# - Units 15H,16H, & 17H								
Combined Softwood	Sawtimber	Unestimated	Ton	7	1	8	5.6	10.67
Combined Softwood	Non Sawtimber	Unestimated	Ton	N/A	1	9	4.0	100% Sound
Total Quantity		21,504 Ton						

1/ Enter Merchantability Factor (Merch. Factor) or Net Scale in % of Gross Scale, whichever is appropriate.

***Combined softwood under C2.11# called alpine fir for accounting purposes.**

A3 – Timber Designations, applicable to B2.3; acres are approximate:

	Number	Acres
Clearcutting Units (B2.31)		
Specified Road Clearing (B2.32)		20
Overstory Removal Units (B2.33)		
Understory Removal Units (B2.34)		
Individual Trees (B2.35)		317
Incompletely Marked Timber (B2.36)		

A4 - Timber Payment Rates, applicable to B3.1 and B4.0

A4a - For Species and Products to be Paid for at Rates Escalated under B3.2

Not Applicable

A4b - For Species and Products to be Paid for at Flat Rates

Species	Product	Unit of Measure	Rates per Unit of Measure				
			Base $	Advertised $	Bid Premium $	Bid (Flat) $	Required Deposits Slash Disposal $
Combined Softwood	Sawtimber	Ton	1.92	7.80			2.70
Combined Softwood	Non-Saw	Ton	1.92	7.80			2.70
Timber Subject to Agreement under C2.11#							
Subalpine Fir	Sawtimber	Ton	1.89	1.89			.85
Subalpine Fir	Non-Saw	Ton	1.89	1.89			.85

For purposes of convenience in collection and bookkeeping, Bid Rates stated in A4 include payment of deposits for sale area betterment required pursuant to 16 USC 576b. Such deposits are not included as Required Deposits defined hereunder.

The following definitions are established for the terms used in A4:

Base Rates are the lowest rates of payment for timber that are authorized by this contract. Base Rates remain constant throughout the life of this contract and are not subject to change by rate redetermination, except for reduction under B3.31, B3.32, or B3.33.

Advertised Rates are the minimum acceptable Bid Rates for timber, exclusive of Required Deposits. These rates are those indicated by appraisal, with a cost allowance made for construction of Specified Roads listed in A7, but are never less than Base Rates.

Bid Premium Rates are the amounts by which Purchaser's bid is in excess of Advertised Rates. The Bid Premium Rates are constant during this contract, except as provided in B3.31, B3.32, and B3.33.

Bid Rates are the rates bid by Purchaser (exclusive of Required Deposits for slash disposal, road maintenance, and contract scaling) and are the sum of Advertised Rates and Bid Premium Rates. Until a rate redetermination becomes effective, the Bid Rate for species and products in A4a is the Tentative Rate that is subject to quarterly adjustment under B3.2; for species and products in A4b, the Bid Rate is the Flat Rate.

Required Deposits are deposits that Purchaser may be required to pay for slash disposal (16 USC 490), road maintenance (16 USC 537), and contract scaling (1994 Appropriations Act). Required Deposits may be adjusted as part of a rate redetermination or a Contract Term Extension. The table shows only Required Deposits for slash disposal; road maintenance deposits, if any, are given in C5.32#; and contract scaling deposits, if any, are given in C6.816#.

Base Index is the specified average of the lumber or other product selling value index used as the basis for computing adjustment in rates for variance in product selling value, as provided in B3.2.

A5 - Indices Used in Quarterly Adjustment, applicable to B3.2

Not Applicable

A6 - High Stumps, applicable to B6.412

Species	Product	Maximum Stump Height (inches)
All	All	12

A7 - Specified Roads, applicable to B5.2

Name and Date of Governing Road Specifications: Forest Service Standard Specifications for Construction of Roads & Bridges (1985), as amended and supplemented (english)

Project		Design Class	Appro. Length (mi./km.)	Sheet Numbers and Approval Date	Performance Responsibility		
Road No.	Name				Survey	Design	Construction Staking 1/
504F	Cedar Shake (C) (segment 0 to .92)	Single Lane - 15 mph	.57 / .92	1.-35 02/20/2008	FS	FS	Purchaser BC
3321E	Christmas Bell (C) (segment 0 to .43)	Single Lane - 15 mph	.27 / .43	1-35 02/20/2008	FS	FS	Purchaser BC
3321B.2	Christmas Carol (C) (segment 0 to .97)	Single Lane - 15 mph	.6 / .97	1-35 02/20/2008	FS	FS	Purchaser BC
3321C.2	Christmas Jingle (C) (segment 0 to .84)	Single Lane - 15 mph	.52 / .84	1-35 02/20/2008	FS	FS	Purchaser BC
3335C	Misfire (C) (segment 0 to .8)	Single Lane - 15 mph	.5 / .8	1-35 02/20/2008	FS	FS	Purchaser BC
504E	Parallel (C) (segment 0 to 1.82)	Single Lane - 15 mph	1.13 / 1.82	1-35 02/20/2008	FS	FS	Purchaser BC
3557	Cedar Butte (R) (segment 0 to .53)	Single Lane - 15 mph	.33 / .53	1-35 02/20/2008	FS	FS	FS BC
3557A	Cedar Butte A Spur (R) (segment 0 to .4)	Single Lane - 15 mph	.25 / .4	1-35 02/20/2008	FS	FS	FS BC
3321B.1	Christmas Carol (R) (segment 0 to 1.53)	Single Lane - 15 mph	.95 / 1.53	1-35 02/20/2008	FS	FS	FS BC
3321C.1	Christmas Jingle (R) (segment 0 to .71)	Single Lane - 15 mph	.44 / .71	1-35 02/20/2008	FS	FS	FS BC
3321A	Christmas Time (R) (segment 0 to .58)	Single Lane - 15 mph	.36 / .58	1-35 02/20/2008	FS	FS	Purchaser BC
504G	Clarkia Overlook (R) (segment 0 to 1.21)	Single Lane - 15 mph	.75 / 1.21	1-35 02/20/2008	FS	FS	FS BC
504A	Clarkia Peak (R) (segment 0 to 1.93)	Single Lane - 25 mph	1.2 / 1.93	1-35 02/20/2008	FS	FS	Purchaser BC

1/ Indicate timing, i.e., before clearing (BC) or after clearing (AC). Applicable to B5.212.

A8 - Forest Service Engineering Completion Schedule, applicable to B5.21

Road No.	Road Name	Type of Work	Completion Date
	NOT APPLICABLE		

A9 - Scaling Instructions and Specifications, applicable to B6.8

Name and Date of Governing Instructions: FSH2409.11a, National Forest Cubic Log Scaling Handbook, as amended and supplemented. Governing instructions for products contained in C Provisions as follows:C6.822, C6.823, C6.840,C6.849

Scaling Specifications					
Species	Product	Maximum Scaling Length (feet)	Trim Allowance		
			Diameter Range (inches)	Length Range (feet)	Trim Allowance (inches)
All	*All*	*99*	*ALL*	*ALL*	*0*

A10 - Scaling Services, applicable to B6.81

Species	Product	Unit of Measure	Site and Geographic Location	Method	Standard Estimated Cost per Unit $
All	All	Ton	Forest Service approved locations with State Certified Scales	Total (100%) Weight Scale	.00

A11 - Minimum Scaling Volumes, applicable to B6.81

Minimum volume for Continuous Scaling Services in two-week period N/A Ton per scaler

Minimum volume for Intermittent Scaling Services N/A Ton on a N/A basis

A12 - Fire Precautionary Period, applicable to B7.2

May 10 to October 20, inclusive

A13 - Purchaser Responsibility to Furnish Crews and Equipment for:

Initial Fire Supression, applicable to B7.3

Within 35 road miles

Fire Suppression Reinforcement, applicable to B7.312 and B 7.313

Within 35 road miles

A14 - Purchaser's Obligation per Operations Fire, applicable to B7.41

Maximum Amount: $ $26,300.00

A15 - Termination Date, applicable to B8.2

October 31, 2013

A16 - Normal Operating Season, applicable to B6.31, B6.66, B8.21 and B9.3

First Period: June 01 to October 15, inclusive

Second Period: _____ to _____, inclusive

A17 - Performance Bond Amount, applicable to B9.1

_____

A18 - Downpayment, applicable to B4.211

Downpayment Amount: _____

A19 - Periodic Payment Amount, applicable to B4.213

	Periodic Payment Determination Date	Amount
Initial Payment:	April 23, 2012	_____
Additional Payment:	April 23, 2013	_____

A20 - Market-Related Contract Term Addition Producer Price Index, applicable to B8.212

Index Name: Softwood Lumber **Index Number:** 0811

A21 – Inapplicable Standard Provisions

The following listed Sections, Subsections, or Items of Division B – Standard Provisions – are hereby made inapplicable. (Instructions: List by reference number and title.)

B2.35 – Individual Trees
B4.211 -- Downpayment
B6.23 – Protection of Land Survey Monuments
B6.35 – Equipment Cleaning
B6.84 – Accountability
B6.841 – Route of Haul
B6.85 – Scaling Lost Products

A22 – List of Special Provisions

The following listed special provisions are attached to and made a part of this contract as Division C. Provisions with reference numbers followed by # contain blanks into which data have been entered for this sale. (Instructions: List by reference number, title, and date.)

See Attached List.

C2.11# – TIMBER SUBJECT TO AGREEMENT. (2/71)
C2.2 - UTILIZATION AND REMOVAL OF INCLUDED PRODUCTS (4/03)
C2.301# - DESIGNATION OF RESERVE TREES. (5/04)
C2.303# - - DEAD TREES. (10/04)
C2.358# - INDIVIDUAL TREES (LEAVE TREE MARKING). (10/04)
C2.359# - INDIVIDUAL TREES (CUT TREE MARKING). (10/04)
C2.38# - SPECIES DESIGNATION. (2/02)
C5.113# - USE AGREEMENT BETWEEN FOREST SERVICE AND OWNER. (7/85)
C5.12# – USE OF ROADS BY PURCHASER. (6/99)
C5.123# - ROAD USE, LIABILITY INSURANCE. (3/90)
C5.13# – ROAD COMPLETION DATE. (4/04)
C5.210 – STAKING ERRORS BY PURCHASER. (10/04)
C5.31# – ROAD MAINTENANCE REQUIREMENTS. (7/01)
C5.315# - ROAD MAINTENANCE ON JOINT OWNERSHIP ROADS. (10/04)
C5.316# - SNOW REMOVAL. (02/02)
C5.32# – ROAD MAINTENANCE DEPOSIT SCHEDULE. (7/01)
C5.41# - CLOSURE TO USE BY OTHERS. (3/07)
C5.419# – SYSTEM ROAD STABILIZATION (3/07)
C6.10 - PREWORK CONFERENCE. (10/04)
C6.23 - PROTECTION OF LAND SURVEY MONUMENTS. (10/04)
C6.316# - LIMITED OPERATING PERIOD. (5/05)
C6.320# –RESERVE TREE PROTECTION. (10/04)
C6.331 - SAFETY (HELICOPTER OPERATIONS). (10/04)
C6.332 - SAFETY (TIMBER HAULING). (10/04)
C6.339 – ACCIDENT AND INJURY NOTIFICATION (4/05)
C6.351 # – WASHING EQUIPMENT. (7/07)
C6.4# - CONDUCT OF LOGGING. (10/82)
C6.406# - SITE CONDITION. (10/01)
C6.41# - SPECIAL FELLING REQUIREMENTS. (10/04)
C6.422 - HELICOPTER LANDING LOCATION AND CONSTRUCTION. (5/76)
C6.6 - EROSION PREVENTION AND CONTROL. (10/04)
C6.601# - EROSION CONTROL SEEDING. (3/07)
C6.661 - CURRENT OPERATING AREAS. (10/04)
C6.7 - HAZARD REDUCTION AND SITE PREPARATION. (3/89)
C6.71 - CHANGE IN SLASH TREATMENTS. (3/90)
C6.711 - BURNING BY PURCHASER. (10/79)
C6.822# - PRESENTATION FOR WEIGHT SCALING . (3/07)
C6.823 - VOLUME DETERMINATION. (10/04)
C6.840- WEIGHT ACCOUNTABILITY. (10/04)
C6.849 - ROUTE OF HAUL. (10/04)
C6.929 - REQUIREMENT FOR FOREST PRACTICES ACT NOTIFICATION. (10/01),
C7.2 - NORMAL PRECAUTIONS. (2/02)
C7.201 - FIRE PRECAUTIONS (HELICOPTER). (2/05)
C8.66# – USE OF TIMBER. (4/04)

SCHEDULE OF ITEMS
(Timber Sale)

Timber Sale: Cedar Side Boards

Road No.: 504A

Road Name: Clarkia Peak

Length (Miles): 1.20 (R)

Item Number	Description	Method of Meas.	Unit	Quantity	S.R.C Unit Price	Total
173(01)A	Establish Slope Stakes, Cut Side(s) & Through Fills, Clearing Limit & Slope Stake Combined	D.Q.	Mile	0.03	$ 988.60	$ 29.66
201(03)	Clearing & Grubbing, Slash Treatment Methods for Tops & Limbs 4, 6.1, 11.3, Log 8.1, & Stumps 4, 11.3, Utilization of Timber 1	D.Q.	Mile	0.03	$ 540.74	$ 16.22
201(08)	Individual Removal of Trees, Miscellaneous; Slash Treatment Methods for Top & Limbs 4, 11.3, & Logs 8.1, Utilization of Timber 1	A.Q.	Each	86.00	$ 35.09	$ 3,017.74
201(09)	Individual Removal of Stumps, Slash Treatment Methods 4, 11.3	A.Q.	Each	31.00	$ 43.86	$ 1,359.66
201A(01)	Roadway Brushing	D.Q.	Mile	1.17	$ 426.88	$ 499.45
203(01)H	Excavation Placement Method 1, Includes Sta. Yd. Haul	D.Q.	C.Y.	284.00	$ 1.88	$ 533.92
204(01)	Temporary Seeding and Fertilizing	D.Q.	Acre	0.16	$ 322.81	$ 51.65
306(01)	Reconditioning of Roadbed, Compaction A	D.Q.	Mile	1.17	$ 691.23	$ 808.74
601(01)	Mobilization	L.S.Q.	L.S.	1.00	$ 526.32	$ 526.32
603(01)18C	18" CMP (incl culv exc), Thickness: Steel 0.064 Thickness: Aluminum 0.060, Method C	A.Q.	L.F.	36.00	$ 21.93	$ 789.48
625(07)	Seeding, Dry Method (With Mulch)	D.Q.	Acre	0.16	$ 778.95	$ 124.63

SUB-TOTAL: $ 7,757.47

TOTAL ALL ROADS: $ 177,422.36

SCHEDULE OF ITEMS
(Timber Sale)

Timber Sale: Cedar Side Boards | Road No.: 504E

Road Name: Parallel | Length (Miles): 1.13 (C)

Item Number	Description	Method of Meas.	Unit	Quantity	S.R.C Unit Price	Total
173(01)A	Establish Slope Stakes, Cut Side(s) & Through Fills, Clearing Limit & Slope Stake Combined	D.Q.	Mile	1.13	$ 962.28	$ 1,087.38
201(01)	Clearing & Grubbing, Slash Treatment Methods for Tops & Limbs 11.1, Logs 8.1, & Stumps 11.1, Utilization of Timber 1	D.Q.	Acre	5.51	$ 2,173.68	$ 11,976.98
203(01)H	Excavation Placement Method 1, Includes Sta. Yd. Haul	D.Q.	C.Y.	7,488.00	$ 1.66	$ 12,430.08
204(01)	Temporary Seeding and Fertilizing	D.Q.	Acre	4.63	$ 322.81	$ 1,494.61
304(10)	Crushed Aggregate, Type Surfacing, Grading D, Compaction B, (commercial source)	D.Q.	C.Y.	1,852.00	$ 19.79	$ 36,651.08
601(01)	Mobilization	L.S.Q.	L.S.	1.00	$ 4,824.56	$ 4,824.56
603(01)18C	18" CMP (incl culv exc), Thickness: Steel 0.064 Thickness: Aluminum 0.060, Method C	A.Q.	L.F.	68.00	$ 19.30	$ 1,312.40
625(07)	Seeding, Dry Method (With Mulch)	D.Q.	Acre	4.63	$ 778.95	$ 3,606.54

SUB-TOTAL: $ 73,383.63

TOTAL ALL ROADS: $ 177,422.36

SCHEDULE OF ITEMS

(Timber Sale)

Timber Sale	Cedar Side Boards	Road No.	504F
Road Name	Cedar Shake	Length (Miles)	0.57 (C)

Item Number	Description	Method of Meas.	Unit	Quantity	S.R.C Unit Price	Total
173(01)A	Establish Slope Stakes, Cut Side(s) & Through Fills, Clearing Limit & Slope Stake Combined	D.Q.	Mile	0.57	$ 962.28	$ 548.50
201(01)	Clearing & Grubbing, Slash Treatment Methods for Tops & Limbs 11.1, Logs 8.1, & Stumps 11.1, Utilization of Timber 1	D.Q.	Acre	3.00	$ 2,173.68	$ 6,521.04
203(01)H	Excavation Placement Method 1, Includes Sta. Yd. Haul	D.Q.	C.Y.	4,292.00	$ 1.66	$ 7,124.72
204(01)	Temporary Seeding and Fertilizing	D.Q.	Acre	2.58	$ 322.81	$ 832.85
601(01)	Mobilization	L.S.Q.	L.S.	1.00	$ 1,228.07	$ 1,228.07
625(07)	Seeding, Dry Method (With Mulch)	D.Q.	Acre	2.58	$ 778.95	$ 2,009.69

SUB-TOTAL: $ 18,264.87

TOTAL ALL ROADS: $ 177,422.36

SCHEDULE OF ITEMS
(Timber Sale)

Timber Sale: Cedar Side Boards

Road No.: 504G

Road Name: Clarkia Overlook

Length (Miles): 0.75 (R)

Item Number	Description	Method of Meas.	Unit	Quantity	S.R.C Unit Price	Total
201(03)	Clearing & Grubbing, Slash Treatment Methods for Tops & Limbs 4, 6.1, 11.3, Log 8.1, & Stumps 4, 11.3, Utilization of Timber 1	D.Q.	Mile	0.75	$ 540.74	$ 405.56
306(01)	Reconditioning of Roadbed, Compaction A	D.Q.	Mile	0.75	$ 691.23	$ 518.42
601(01)	Mobilization	L.S.Q.	L.S.	1.00	$ 438.60	$ 438.60

SUB-TOTAL: $ 1,362.58

TOTAL ALL ROADS: $ 177,422.36

SCHEDULE OF ITEMS
(Timber Sale)

Timber Sale: Cedar Side Boards

Road No.: 3321A

Road Name: Christmas Time

Length (Miles): 0.36 (R)

Item Number	Description	Method of Meas.	Unit	Quantity	S.R.C Unit Price	Total
173(01)A	Establish Slope Stakes, Cut Side(s) & Through Fills, Clearing Limit & Slope Stake Combined	D.Q.	Mile	0.36	$ 988.60	$ 355.90
201(01)	Clearing & Grubbing, Slash Treatment Methods for Tops & Limbs 11.1, Logs 8.1, & Stumps 11.1, Utilization of Timber 1	D.Q.	Acre	1.70	$ 428.84	$ 729.03
202(02)CM	Removal of Metal Pipe	A.Q.	Each	1.00	$ 166.67	$ 166.67
203(01)H	Excavation Placement Method 1, Includes Sta. Yd. Haul	D.Q.	C.Y.	627.00	$ 1.88	$ 1,178.76
203(10)	Borrow Excavation, Placement Method 1	D.Q.	C.Y.	714.00	$ 12.85	$ 9,174.90
204(01)	Temporary Seeding and Fertilizing	D.Q.	Acre	1.30	$ 322.81	$ 419.65
204(09)	Sediment Basin	A.Q.	Each	1.00	$ 78.95	$ 78.95
601(01)	Mobilization	L.S.Q.	L.S.	1.00	$ 1,052.63	$ 1,052.63
603(01)24C	24" CMP (incl culv exc), Thickness: Steel 0.064 Thickness: Aluminum 0.060, Method C	A.Q.	L.F.	36.00	$ 25.44	$ 915.84
625(07)	Seeding, Dry Method (With Mulch)	D.Q.	Acre	1.30	$ 778.95	$ 1,012.64

SUB-TOTAL: $ 15,084.97

TOTAL ALL ROADS: $ 177,422.36

SCHEDULE OF ITEMS
(Timber Sale)

Timber Sale: Cedar Side Boards

Road No.: 3321B.1

Road Name: Christmas Carol

Length (Miles): 0.95 (R)

Item Number	Description	Method of Meas.	Unit	Quantity	S.R.C Unit Price	Total
201(03)	Clearing & Grubbing, Slash Treatment Methods for Tops & Limbs 4, 6.1, 11.3, Log 8.1, & Stumps 4, 11.3, Utilization of Timber 1	D.Q.	Mile	0.95	$ 540.74	$ 513.70
306(01)	Reconditioning of Roadbed, Compaction A	D.Q.	Mile	0.95	$ 691.23	$ 656.67
601(01)	Mobilization	L.S.Q.	L.S.	1.00	$ 438.60	$ 438.60
603(01)18C	18" CMP (incl culv exc), Thickness: Steel 0.064 Thickness: Aluminum 0.060, Method C	A.Q.	L.F.	32.00	$ 21.93	$ 701.76

SUB-TOTAL: $ 2,310.73

TOTAL ALL ROADS: $ 177,422.36

SCHEDULE OF ITEMS
(Timber Sale)

Timber Sale: Cedar Side Boards

Road No.: 3321B.2

Road Name: Christmas Carol

Length (Miles): 0.60 (C)

Item Number	Description	Method of Meas.	Unit	Quantity	S.R.C Unit Price	Total
173(01)A	Establish Slope Stakes, Cut Side(s) & Through Fills, Clearing Limit & Slope Stake Combined	D.Q.	Mile	0.60	$ 962.28	$ 577.37
201(01)	Clearing & Grubbing, Slash Treatment Methods for Tops & Limbs 11.1, Logs 8.1, & Stumps 11.1, Utilization of Timber 1	D.Q.	Acre	2.78	$ 2,173.68	$ 6,042.83
203(01)H	Excavation Placement Method 1, Includes Sta. Yd. Haul	D.Q.	C.Y.	2,763.00	$ 1.66	$ 4,586.58
204(01)	Temporary Seeding and Fertilizing	D.Q.	Acre	2.25	$ 322.81	$ 726.32
601(01)	Mobilization	L.S.Q.	L.S.	1.00	$ 1,052.63	$ 1,052.63
603(01)18C	18" CMP (incl culv exc), Thickness: Steel 0.064 Thickness: Aluminum 0.060, Method C	A.Q.	L.F.	32.00	$ 19.30	$ 617.60
625(07)	Seeding, Dry Method (With Mulch)	D.Q.	Acre	2.25	$ 778.95	$ 1,752.64

SUB-TOTAL: $ 15,355.97

TOTAL ALL ROADS: $ 177,422.36

SCHEDULE OF ITEMS
(Timber Sale)

Timber Sale: Cedar Side Boards

Road No.: 3321C.1

Road Name: Christmas Jingle

Length (Miles): 0.44 (R)

Item Number	Description	Method of Meas.	Unit	Quantity	S.R.C Unit Price	Total
201(03)	Clearing & Grubbing, Slash Treatment Methods for Tops & Limbs 4, 6.1, 11.3, Log 8.1, & Stumps 4, 11.3, Utilization of Timber 1	D.Q.	Mile	0.44	$ 540.74	$ 237.93
306(01)	Reconditioning of Roadbed, Compaction A	D.Q.	Mile	0.44	$ 691.23	$ 304.14
601(01)	Mobilization	L.S.Q.	L.S.	1.00	$ 438.60	$ 438.60
603(01)18C	18" CMP (incl culv exc), Thickness: Steel 0.064 Thickness: Aluminum 0.060, Method C	A.Q.	L.F.	64.00	$ 21.93	$ 1,403.52

SUB-TOTAL: $ 2,384.19

TOTAL ALL ROADS: $ 177,422.36

SCHEDULE OF ITEMS

(Timber Sale)

Timber Sale	Cedar Side Boards	Road No.	3321C.2
Road Name	Christmas Jingle	Length (Miles)	0.52 (C)

Item Number	Description	Method of Meas.	Unit	Quantity	S.R.C Unit Price	Total
173(01)A	Establish Slope Stakes, Cut Side(s) & Through Fills, Clearing Limit & Slope Stake Combined	D.Q.	Mile	0.52	$ 962.28	$ 500.39
201(01)	Clearing & Grubbing, Slash Treatment Methods for Tops & Limbs 11.1, Logs 8.1, & Stumps 11.1, Utilization of Timber 1	D.Q.	Acre	2.29	$ 2,173.68	$ 4,977.73
203(01)H	Excavation Placement Method 1, Includes Sta. Yd. Haul	D.Q.	C.Y.	2,053.00	$ 1.66	$ 3,407.98
204(01)	Temporary Seeding and Fertilizing	D.Q.	Acre	1.79	$ 322.81	$ 577.83
601(01)	Mobilization	L.S.Q.	L.S.	1.00	$ 964.91	$ 964.91
603(01)18C	18" CMP (incl culv exc), Thickness: Steel 0.064 Thickness: Aluminum 0.060, Method C	A.Q.	L.F.	100.00	$ 19.30	$ 1,930.00
625(07)	Seeding, Dry Method (With Mulch)	D.Q.	Acre	1.79	$ 778.95	$ 1,394.32

SUB-TOTAL: $ 13,753.16

TOTAL ALL ROADS: $ 177,422.36

SCHEDULE OF ITEMS
(Timber Sale)

Timber Sale: Cedar Side Boards

Road No.: 3321E

Road Name: Christmas Bell

Length (Miles): 0.27 (C)

Item Number	Description	Method of Meas.	Unit	Quantity	S.R.C Unit Price	Total
173(01)A	Establish Slope Stakes, Cut Side(s) & Through Fills, Clearing Limit & Slope Stake Combined	D.Q.	Mile	0.27	$ 962.28	$ 259.82
201(01)	Clearing & Grubbing, Slash Treatment Methods for Tops & Limbs 11.1, Logs 8.1, & Stumps 11.1, Utilization of Timber 1	D.Q.	Acre	1.34	$ 2,173.68	$ 2,912.73
203(01)H	Excavation Placement Method 1, Includes Sta. Yd. Haul	D.Q.	C.Y.	1,475.00	$ 1.66	$ 2,448.50
204(01)	Temporary Seeding and Fertilizing	D.Q.	Acre	1.12	$ 322.81	$ 361.55
601(01)	Mobilization	L.S.Q.	L.S.	1.00	$ 526.32	$ 526.32
625(07)	Seeding, Dry Method (With Mulch)	D.Q.	Acre	1.12	$ 778.95	$ 872.42

SUB-TOTAL: $ 7,381.34

TOTAL ALL ROADS: $ 177,422.36

SCHEDULE OF ITEMS
(Timber Sale)

Timber Sale: Cedar Side Boards

Road No.: 3335C

Road Name: Misfire

Length (Miles): 0.50 (C)

Item Number	Description	Method of Meas.	Unit	Quantity	S.R.C Unit Price	Total
173(01)A	Establish Slope Stakes, Cut Side(s) & Through Fills, Clearing Limit & Slope Stake Combined	D.Q.	Mile	0.50	$ 962.28	$ 481.14
201(01)	Clearing & Grubbing, Slash Treatment Methods for Tops & Limbs 11.1, Logs 8.1, & Stumps 11.1, Utilization of Timber 1	D.Q.	Acre	2.46	$ 2,173.68	$ 5,347.25
203(01)H	Excavation Placement Method 1, Includes Sta. Yd. Haul	D.Q.	C.Y.	3,008.00	$ 1.66	$ 4,993.28
204(01)	Temporary Seeding and Fertilizing	D.Q.	Acre	2.05	$ 322.81	$ 661.76
601(01)	Mobilization	L.S.Q.	L.S.	1.00	$ 1,140.35	$ 1,140.35
603(01)18C	18" CMP (incl culv exc), Thickness: Steel 0.064 Thickness: Aluminum 0.060, Method C	A.Q.	L.F.	122.00	$ 19.30	$ 2,354.60
625(07)	Seeding, Dry Method (With Mulch)	D.Q.	Acre	2.05	$ 778.95	$ 1,596.85

SUB-TOTAL: $ 16,575.23

TOTAL ALL ROADS: $ 177,422.36

SCHEDULE OF ITEMS
(Timber Sale)

Timber Sale: Cedar Side Boards

Road No.: 3557

Road Name: Cedar Butte

Length (Miles): 0.33 (R)

Item Number	Description	Method of Meas.	Unit	Quantity	S.R.C Unit Price	Total
201(03)	Clearing & Grubbing, Slash Treatment Methods for Tops & Limbs 4, 6.1, 11.3, Log 8.1, & Stumps 4, 11.3, Utilization of Timber 1	D.Q.	Mile	0.33	$ 1,363.84	$ 450.07
203(08)	Excavation, Placement Method 1	D.Q.	Mile	0.33	$ 1,223.59	$ 403.78
204(01)	Temporary Seeding and Fertilizing	D.Q.	Acre	0.76	$ 322.81	$ 245.34
601(01)	Mobilization	L.S.Q.	L.S.	1.00	$ 438.60	$ 438.60
625(07)	Seeding, Dry Method (With Mulch)	D.Q.	Acre	0.76	$ 778.95	$ 592.00

SUB-TOTAL: $ 2,129.79

TOTAL ALL ROADS: $ 177,422.36

SCHEDULE OF ITEMS
(Timber Sale)

Timber Sale: Cedar Side Boards

Road No.: 3557A

Road Name: Cedar Butte A Spur

Length (Miles): 0.25 (R)

Item Number	Description	Method of Meas.	Unit	Quantity	S.R.C Unit Price	Total
601(01)	Mobilization	L.S.Q.	L.S.	1.00	$ 131.58	$ 131.58
640(01)	Furnish and Install Road Closure Device, Type Gate, Size 14'0" - 16'6"	A.Q.	Each	1.00	$ 1,546.85	$ 1,546.85

SUB-TOTAL: $ 1,678.43

TOTAL ALL ROADS: $ 177,422.36